

KEYNOTES

- NOTE: ITEMS IDENTIFIED ARE TYPICAL TO ALL LIKE ITEMS UNLESS NOTED OTHERWISE
- 01 - GENERAL REQUIREMENTS**
- 02 - NOT USED**
- 03 - CONCRETE**
- 3.01 CONC. SLAB ON GRADE, LIGHT BROOM FINISH AT PARKING GARAGE, TYP.
- 3.02 PRE-CAST CONC. STAIR TREADS/LANDING
- 3.03 CONC. STRUCT'L SLAB, SLOPE TO DRAIN AT INDICATED AREAS, BUFF FLAT/SMOOTH AND CLEAR SEAL AT LOBBY AND COMMERCIAL SPACES
- 3.04 CONC. WALL
- 3.05 CONC. COLUMNS
- 3.06 CONC. FOUNDATION
- 3.07 CONC. GUARDRAIL, 3'-7" HIGH
- 3.08 CONC. STAIR/STEPS
- 3.09 6" TALL X 6" U.N.O. WIDE CONC. CURB
- 3.10 CONC. WHEEL STOP
- 3.11 CONC. PLANTER
- 04 - MASONRY**
- 4.01 CMU WALL PER STRUCT'L
- 4.02 NON-BEARING CMU WALL W/ 2" CMU CAP @ EXTERIOR LOCATION
- 05 - METALS**
- 5.01 STEEL COLUMN, SEE STRUCTURAL
- 5.02 STEEL TRELLIS, SEE STRUCTURAL
- 5.03 STEEL STAIR CHANNEL STRINGERS/SOLID RISER
- 5.04 STEEL PIPE HANDRAIL, PAINTED
- 5.05 5" DIA. CONCRETE FILLED GALV. PIPE BOLLARD PER S&P 31
- 5.06 GUARDRAIL, PAINTED, MIN 3'-6" HIGH ABOVE FINISH DECK, SEE DETAILS
- 5.07 2X8 MTL. STUD FURRED PLUMBING WALL
- 5.08 METAL STUD WALL FRAMING, TYP. @ GROUND FLOOR
- 06 - WOODS & PLASTIC**
- 6.01 WOOD POST
- 6.02 WOOD BEAMJOIST
- 6.03 WOOD WALL FRAMING WITH PLY SHEAR WHERE OCCURS
- 6.04 WOOD TYP. FLOOR JOIST
- 6.05 MIN. 5/8" PLY OVER 2X WD RIP STRIPS FOR ROOF SLOPE AND/OR CRICKET
- 6.06 RUBBER WALL BASE
- 6.07 SOLID SURFACE COUNTERTOP BY 'LG HI-MACS' BLACK TYP. @ KITCHENS, BATHROOMS, AND LAUNDRY ROOM
- 6.08 WOOD WALL BASE, PAINTED
- 6.09 WOOD CABINETS: BEECH FACES, SOLID FLAT DOORS, EUROPEAN CONCEALED HINGES AND SELF CLOSE DRAWERS. CASEWORK SHALL BE 'CUSTOM GRADE' FOR MATERIAL, HARDWARE, JOINERY AND INSTALLATION, TYP.
- 6.10 WOOD MDF SHELF
- 6.11 WOOD POLE CLOTHES ROD, DOUGLAS FIR, 1-3/8" DIA, PAINTED
- 07 - THERMAL & MOISTURE PROTECTION**
- 7.01 DECK COATINGS OVER STRUCTURAL SLAB OR PLYWOOD
- 7.02 THERMAL BATT INSULATION, R-21MIN @ WALLS, R-38 MIN @ ROOF
- 7.03 W.P. MEMBRANE
- 7.04 VAPOR PERMEABLE MEMBRANE AIR BARRIER AT EXTERIOR WALLS, TYP.
- 7.05 SINGLE-PLY PVC WHITE SHEET ROOFING, FLOOR OR DECK DRAIN
- 7.06 SCUPPER
- 7.07 UNDERSLAB MOISTURE VAPOR BARRIER
- 7.08 ROOF DRAIN
- 7.09 18 GA. 'BONDERIZED' METAL COPING, PTD, TYP. AT ALL FRAMED PARAPETS
- 7.10 PLASTER CONTROL JOINT PER DETAIL
- 08 - OPENINGS (SEE DOOR/WINDOW SCHEDULE)**
- 8.01 VINYL WINDOW, PER SPECS
- 8.02 ALUM. STOREFRONT, PER SPECS.
- 8.03 TRANSOM WINDOW, PER SPECS.
- 8.04 ALUM. STOREFRONT DOOR, PER SPECS
- 8.05 STL. DOOR & FRAME, PER SPECS.
- 8.06 SLIDING DOOR, PER SPECS
- 8.07 SOLID WOOD DOOR, SPEC SPECS
- 8.08 INTERIOR WOOD DOOR, PER SPECS
- 8.09 CLOSET DOOR, PTD
- 8.10 ACCESS PANEL, COLOR AND MATERIAL SHALL MATCH ADJACENT MATERIAL
- 8.11 DOOR HARDWARE SET PER SCHEDULE
- 8.12 EXTERIOR WALL LOUVER
- 8.13 EXTERIOR WALL VENT CAP
- 09 - FINISHES (SEE FINISH SCHEDULE)**
- 9.01 NOT USED
- 9.02 7/8" PERFORATED CORRUGATED MTL. ALUM. PANELS, PTD.
- 9.03 7/8" INTEGRAL COLOR EXT. CEMENT PLASTER OVER MTL. LATH & BUILDING PAPER, SEE ELEVATIONS/DETAILS FOR 'SPARKLE' ADDITIVE AND FURRED SCALLOPING
- 9.04 5/8" TYPE 'X' GYP BOARD, TYP. PROVIDE AS 'EXTERIOR' OR 'WET RATED' AS REQUIRED
- 9.05 NOT USED
- 9.06 VINYL PLANK FLOORING
- 9.07 CERAMIC TILE
- 9.08 GRAFFITI COATING, TYP. @ ALL EXTERIOR SOLID WALLS FROM GRADE UP TO SECOND FLOOR DECK
- 9.09 2' X 2' ACOUSTICAL SUSPENDED CEILING SYSTEM
- 9.10 SUSPENDED GYP. BOARD CEILING
- 10 - SPECIALTIES (SEE SPECS/ACCESSORY SCHEDULE)**
- 10.01 MIRROR, WALL MOUNTED
- 10.02 SIGNAGE
- 10.03 MAILBOXES, FRONT LOAD, RECESSED, PROVIDE FOR 35 UNITS PLUS 2 COMM.
- 10.04 TOILET PAPER ROLL HOLDER
- 10.05 SHOWER CURTAIN ROD
- 10.06 TOWEL BAR
- 10.07 ROBE HOOK
- 10.08 RECESSED MEDICINE CABINET, W/ FLUSH PAINTED DOOR
- 10.09 FIRE EXTINGUISHER, SURFACE MOUNT IN GARAGE, RECESSED CABINET ELSEWHERE
- 10.10 RECESSED, EXTERIOR UNIT ENTRY INTERCOM SYSTEM AND MOUNTING HARDWARE
- 10.11 GRAB BAR
- 11 - EQUIPMENT/APPLIANCES (SEE EQMT. SCHEDULE)**
- 11.01 REFRIGERATOR, CFCI
- 11.02 GAS RANGE/OVEN, CFCI
- 11.03 KITCHEN RANGE EXHAUST HOOD, CFCI
- 11.04 DISHWASHER, CFCI
- 11.05 CLOTHES WASHER, OFCI
- 11.06 DRYER, OFCI
- 11.07 TRASH CHUTES: LABEL AS 'REFUSE' AND 'RECYCLABLES'
- 12 - FURNISHINGS**
- 12.01 VERTICAL WINDOW SHADE SLATS, WHITE, TYP. @ ALL UNITS
- 12.02 ROLLING WINDOW SHADE, SEE DETAIL
- 12.03 BICYCLE RACKS FOR LONG TERM BIKE STORAGE
- 12.04 BICYCLE RACK FOR SHORT TERM BIKE PARKING
- 12.05 FURNITURE, N/C
- 13 - SPECIAL CONSTRUCTION (NOT USED)**
- 14 - CONVEYING EQUIPMENT**
- 14.01 THYSSENKRUPP ENDURA HOLELESS HYDRAULIC ELEVATOR, 3,500 LBS., 150 FPM
- 21 - FIRE SUPPRESSION**
- 21.01 NFPA 13 FIRE SPRINKLER RISER AT EACH STAIR, RECESSED
- 21.02 FIRE SPRINKLER HORIZ. MAIN (SEE DIAGRAM)
- 21.03 ROUND FIRE ALARM BELL, ARCHITECT SHALL APPROVE FINAL LOCATION
- 21.04 FIRE DEPARTMENT MAIN CONNECTION @ STAIR, RECESSED
- 21.05 FD ANNUNCIATOR PANEL.
- 22 - PLUMBING**
- 22.01 MOP SINK
- 22.02 KITCHEN SINK/FAUCET
- 22.03 LAV. SINK/FAUCET
- 22.04 PRE-FAB FIBERGLASS BATHTUB
- 22.05 BATH TUB FAUCET
- 22.06 SHOWER HEAD AND CONTROLS
- 22.07 ULTRA LOW FLOW TOILET
- 22.08 BOILER PER PLUMBING DWGS
- 22.09 HOT WATER TANK PER PLUMBING DWGS
- 22.10 ROOF DRAIN OVERFLOW DAYLIGHT SCUPPER, REFER TO DETAIL 11/A9.02
- 22.11 FLOOR DRAIN
- 22.12 PLUMBING VENT PIPE
- 23 - HEATING, VENTILATING, AND AIR-CONDITIONING**
- 23.01 HVAC UNIT PER MECH
- 23.02 AIR REGISTER WALL MOUNTED
- 23.03 CEILING AIR REGISTER
- 23.04 KITCHEN HOOD EXHAUST DUCT
- 23.05 ENERGY STAR RATED BATHROOM EXHAUST FAN PER SPECS
- 23.06 BATHROOM EXHAUST DUCT
- 23.07 MECH. EXHAUST LOUVER, PER MECH.
- 26 - ELECTRICAL**
- 26.01 ROOF AREA FOR FUTURE SOLAR SYSTEM PER 2018 CBC SECT. 110.10.00.13 PROVIDE CONDUIT TO ROOF FOR FUTURE SOLAR SYSTEM
- 26.02 FUTURE ELECTRICAL VEHICLE CHARGING STATION
- 26.03 ELEC. PANEL PER PLANS & SCHEDULE
- 26.04 EXTERIOR LIGHT PER SCHEDULE
- 26.05 INTERIOR LIGHT PER SCHEDULE
- 27 - COMMUNICATION**
- 28 - ELECTRONIC SAFETY AND SECURITY**
- 28.01 SMOKE ALARM
- 28.02 SECURITY CAMERA
- 28.03 FIRE ALARM MAIN PANEL, ARCHITECT SHALL APPROVE FINAL LOCATION
- 31 - EARTHWORK**
- 31.01 APPROVED COMPACT FILL PER GEO AND SOIL ENGINEER REPORT
- 32 - EXTERIOR IMPROVEMENTS**
- 32.01 NEW CONCRETE SIDEWALK
- 32.02 PARKING STALL STRIPING PER CITY OF LA REQUIREMENTS
- 32.03 EPIC STORM WATER SYSTEM, SEE CIVIL
- 32.04 STEEL SECURITY GATE, PTD.
- 32.05 STEEL SECURITY FENCE, PTD.
- 32.06 EXTERIOR PLANTER DRAIN
- 32.07 MOTORIZED STL. OVERHEAD GATE
- 32.08 IPE WOOD TILES
- 32.09 TREE, SEE LANDSCAPE DRAWINGS
- 32.10 PLANTINGS, SEE LANDSCAPE DRAWINGS
- 33 - UTILITIES**
- 33.01 WATER METER
- 33.02 GAS METER, PROTECT W/ BOLLARDS AS REQUIRED
- 33.03 ELECTRIC METERS
- 33.04 DOMESTIC WATER BACKFLOW PREVENTER
- 33.05 FIRE METER BACKFLOW PREVENTER
- 33.06 IRRIGATION BACKFLOW PREVENTER
- 33.07 ELECTRICAL TRANSFORMER IN UNDERGROUND VAULT
- 33.08 SUMP PUMP PER CIVIL

CONCEPTUAL DESIGN	2017-12-01
SCHEMATIC DESIGN	2018-05-10
DESIGN DEVELOPMENT	2018-06-29
50% CONTRUCTION DOCUMENTS	2018-12-14
PLAN CHECK SUBMITTAL (95% CDS)	2019-03-05

PERMIT SET

BID ISSUE

CONSTRUCTION ISSUE

720 ROSE AVE.  
MIXED-USED 35 UNITS

REVISIONS:


SHEET TITLE:  
3RD FLOOR DRAINAGE PLAN

SCALE: As indicated  
DATE PRINTED: 2/28/2019 4:32:15 PM

ALL DRAWINGS AND WRITTEN MATERIAL APPEARING HEREIN CONSTITUTE ORIGINAL AND UNPUBLISHED WORK OF THE ARCHITECT AND MAY NOT BE DUPLICATED, USED OR DISCLOSED WITHOUT THE WRITTEN CONSENT OF THE ARCHITECT.


BROOKS SCARPA ARCHITECTURE  
3929 W. 139TH STREET  
HAWTHORNE, CA. 90250  
t: 323.596.4700  
f: 310.453.9606

A3.32



3RD FLOOR DRAINAGE PLAN

REF : A3.30 SCALE: 1/8" = 1'-0"



TYP PLAN AT 3RD & 4TH FLOOR THRESHOLD

REF : SCALE: 1 1/2" = 1'-0"

GENERAL NOTES - DRAINAGE PLANS

- CROSS SLOPES SHALL BE MAX. OF 2% AND SLOPES IN THE DIRECTION OF TRAVEL SHALL BE 5% MAX.
- ALL SLOPES FOR PLANTER DRAINAGE ARE 2% MIN

PLAN LEGEND

- INDICATES 1/4" STEP
- INDICATES 2% SLOPE MAX
- AD AREA DRAIN
- PD PLANTER DRAIN
- OPENING IN SLAB